LEWISTON ROUNDUP (PWS # 2350016) SOURCE WATER ASSESSMENT FINAL REPORT

March 12, 2002



State of Idaho Department of Environmental Quality

Disclaimer: This publication has been developed as part of an informational service for the source water assessments of public water systems in Idaho and is based on the data available at the time and the professional judgement of the staff. Although reasonable efforts have been made to present accurate information, no guarantees, including expressed or implied warranties of any kind, are made with respect to this publication by the State of Idaho or any of its agencies, employees, or agents, who also assume no legal responsibility for the accuracy of presentations, comments, or other information in this publication. The assessment is subject to modification if new data is produced.

Executive Summary

Under the Federal Safe Drinking Water Act Amendments of 1996, all states are required by the U.S. Environmental Protection Agency (EPA) to assess every source of public drinking water for its relative sensitivity to contaminants regulated by the Act. The Idaho Department of Environmental Quality (DEQ) is completing the assessments for all Idaho public drinking water systems. The assessment for your particular drinking water source is based on a land use inventory within a 1,000-foot radius of your drinking water source, sensitivity factors associated with the source, and characteristics associated with either your aquifer or watershed in which you live.

This report, Source Water Assessment for Lewiston Roundup: Public Water System (PWS) #2350016 describes the public drinking water system, the associated potential contaminant sources located within a 1,000-foot boundary around the drinking water source, and the susceptibility (risk) that may be associated with any associated potential contaminants. This assessment should be used as a planning tool, taken into account with local knowledge and concerns, to develop and implement appropriate protection measures for this system. The results should not be used as an absolute measure of risk and is not intended to undermine the confidence in your water system.

The *Lewiston Roundup* drinking water system consists of three ground water wells. Well #1 and Well #2 have a high susceptibility and Well #3 has a moderate susceptibility to all potential contaminant categories: inorganic contaminants (IOCs), volatile organic contaminants (VOCs), synthetic organic contaminants (SOCs), and microbial contaminants. The high hydrologic sensitivity scores of Well #1 and Well #2 and the predominant agricultural land within the delineated areas contributed to the overall susceptibility of the wells. The moderate hydrologic sensitivity score of Well #3 combined with a limited number of potential contaminants in the delineated area reflect the overall susceptibility for Well #3.

Nitrate has been detected at levels greater than one-half the maximum contaminant (MCL) level of 10 milligrams per liter (mg/L) in Well #1, Well #2, and in the manifold. Well #1 has shown the highest detection with a nitrate level of 9.45 mg/L in April of 1995. In December 1997, nitrate in Well #2 was recorded at 9.2 mg/L. In February 1997, the manifold had a nitrate detection of 7.7 mg/L and in January 2000, nitrate was at 5.3 mg/L in the manifold. Though these levels remain under the MCL, nitrate could become a problem in the future for the Lewiston Roundup drinking water system.

The initial computer generated contaminant source inventory conducted by the DEQ located two potential contaminant sources within the 1,000-foot boundary of Well #1 and Well #2 (Table 1) and it located one potential contaminant source within the 1,000-foot boundary of Well #3 (Table 2). Additionally, the geographic information system (GIS) map shows that Well #1 and Well #2 lie within 1,000 feet of the P2 Highway out of Lewiston and Tammany Creek (Table 1). A copy of the susceptibility analysis worksheet for the Lewiston Roundup drinking water system along with a map showing any potential contaminant sources is included with this summary.

Table 1. Lewiston Roundup Well #1 and Well #2, Potential Contaminant Inventory

SITE#	Source Description ¹	Source of Information	Potential Contaminants ²			
1	Mine	Database Search	IOC, VOC, SOC, Microbials			
2	Group 1 Site-N>10	Database Search	IOC			
	P2 Highway	GIS Map	IOC, VOC, SOC, Microbials			
	Tammany Creek	GIS Map	IOC, VOC, SOC, Microbials			

²IOC = inorganic chemical, VOC = volatile organic chemical, SOC = synthetic organic chemical

Table 2. Lewiston Roundup Well #3, Potential Contaminant Inventory

SITE#	Source Description ¹	Source of Information	Potential Contaminants ²
1	Group 1 Site-N>10	Database Search	IOC

²IOC = inorganic chemical, VOC = volatile organic chemical, SOC = synthetic organic chemical

Susceptibility Analysis

Each well's susceptibility to contamination was ranked as high, moderate, or low risk according to the following considerations: hydrologic characteristics, physical integrity of the well, land use characteristics, and potentially significant contaminant sources. The susceptibility rankings are specific to a particular potential contaminant or category of contaminants. Therefore, a high susceptibility rating relative to one potential contaminant does not mean that the water system is at the same risk for all other potential contaminants. The relative ranking that is derived for each well is a qualitative, screening-level step that, in many cases, uses generalized assumptions and best professional judgement. The following summaries describe the rationale for the susceptibility ranking.

Hydrologic Sensitivity

The hydrologic sensitivity of a well is dependent upon four factors: the surface soil composition, the material in the vadose zone (between the land surface and the water table), the depth to first ground water, and the presence of a 50-foot thick fine-grained zone above the producing zone of the well. Slowly draining soils such as silt and clay typically are more protective of ground water than coarse-grained soils such as sand and gravel. Similarly, fine-grained sediments in the subsurface and a water depth of more than 300 feet protect the ground water from contamination.

The hydrologic sensitivity is high for Well #1 and Well #2 and moderate for Well #3. Regional soil data indicates the presence of moderate to well draining soils. The well logs for Well #1 and Well #2 were unavailable, preventing a determination of depth to first ground water, composition of the vadose zones, and the presence of low permeability units within the vadose zone. The well log for Well #3 indicates that a 55-foot clay layer is present above the producing zone. It also shows that the vadose zone is composed predominantly of basalt.

Well Construction

Well construction directly affects the ability of the well to protect the aquifer from contaminants. System construction scores are reduced when information shows that potential contaminants will have a more difficult time reaching the intake of the well. Lower scores imply a system is less vulnerable to contamination. For example, if the well casing and annular seal both extend into a low permeability unit, then the possibility of contamination is reduced and the system construction score goes down. If the highest production interval is more than 100 feet below the water table, then the system is considered to have better buffering capacity. If the wellhead and surface seal are maintained to standards, as outlined in sanitary surveys, then contamination down the well bore is less likely. If the well is protected from surface flooding and is outside the 100-year floodplain, then contamination from surface events is reduced.

Well #2 and Well #3 of the Lewiston Roundup drinking water system rate moderate and Well #1 rate high for system construction. The 1996 sanitary survey indicates that the wellhead and surface seals are maintained to standards for all of the wells but that only Well #2 and Well #3 are properly protected from surface flooding. The casing of Well #1 only extends 12 inches above ground surface instead of the required 18 inches. The well logs for Well #1 and Well #2 were unavailable, limiting the amount of well construction information for those wells. The well log for Well #3 indicates that the well was drilled in 1992 to a depth of 355 feet below ground surface (bgs). It has an 8-inch casing set to a depth of 78 feet bgs and the static water level is found at 120 feet bgs. Though the wells may have met construction standards at the time of installation, current well construction standards are more stringent.

The Idaho Department of Water Resources *Well Construction Standards Rules* (1993) require all Public Water Systems (PWSs) to follow DEQ standards as well. IDAPA 58.01.08.550 requires that PWSs follow the *Recommended Standards for Water Works* (1997) during construction. Some of the requirements include casing thickness, well tests, and depth and formation type that the surface seal must be installed into. Table 1 of the *Recommended Standards for Water Works* (1997) lists the required steel casing thickness for various diameter wells. Well tests are required at the design pumping rate for 24 hours or until stabilized drawdown has continued for at least six hours when pumping at 1.5 times the design pumping rate.

Potential Contaminant Source and Land Use

Well #1 and Well #2 rated high for IOCs (e.g., arsenic, nitrate) and moderate for VOCs (e.g., petroleum products), SOCs (e.g., pesticides), and microbial contaminants (e.g., bacteria). Well #3 rated moderate for IOCs and low for VOCs, SOCs, and microbial contaminants. The Group 1 Site, a site that showed an elevated level of nitrate (an IOC), and the predominant agricultural land within the delineated areas of the wells contributed to the land use ratings of all of the wells. The P2 highway and Tammany Creek within the 1,000-foot boundary areas of Well #1 and Well #2 also contributed to the land use ratings for those wells.

Final Susceptibility Rating

An IOC detection above a drinking water standard MCL, any detection of a VOC or SOC, or a detection of total coliform bacteria or fecal coliform bacteria at the wellhead will automatically give a high susceptibility rating to a well, despite the land use of the area, because a pathway for contamination already exists. Additionally, having potential contaminant sources within 50 feet of the wellhead will give an automatic high susceptibility rating. Hydrologic sensitivity and system construction scores are heavily weighted in the final scores. Having multiple potential contaminant sources in the 0- to 3-year time-of-travel zone (Zone 1B) and much agricultural land contribute greatly to the overall ranking.

In terms of total susceptibility, Well #1 and Well #2 of the Lewiston Roundup drinking water system have a high susceptibility and Well #3 has a moderate susceptibility to all potential contaminant categories. The predominant agricultural land in the area contributed to the susceptibility of all of the wells. The high hydrologic sensitivity and the highway, creek, and mine that can add leachable chemicals to the aquifer contributed to the overall susceptibility of Well #1 and Well #2. The limited number of contaminants and the protective nature of the aquitard above the producing zone of Well #3 reflects the overall susceptibility of that well. The table below provides a summary of the susceptibility of the system.

Table 3. Summary of Lewiston Roundup Susceptibility Evaluation

	Susceptibility Scores ¹										
	Hydrologic Sensitivity	Contaminant Inventory			System Construction	Final Susceptibility Ranking					
Well		IOC	VOC	SOC	Microbials		IOC	VOC	SOC	Microbials	
Well #1	Н	Н	M	M	M	Н	Н	Н	Н	Н	
Well #2	Н	Н	M	M	M	M	Н	Н	Н	Н	
Well #3	M	M	L	L	L	M	M	M	M	M	

¹H = High Susceptibility, M = Moderate Susceptibility, L = Low Susceptibility,

Options for Drinking Water Protection

This assessment should be used as a basis for determining appropriate new protection measures or re-evaluating existing protection efforts. No matter what ranking a source receives, protection is always important. Whether the source is currently located in a "pristine" area or an area with numerous industrial and/or agricultural land uses, the way to ensure good water quality in the future is to act now to protect valuable water supply resources.

For the Lewiston Roundup system, drinking water protection activities should focus on repairing any deficiencies listed in the sanitary survey and on implementation practices aimed at maintaining well construction to avoid contamination from contaminant sources within the designated source water area. Lewiston Roundup may need to consider using engineering controls to manage or reduce the nitrate levels in Well #1 and Well #2. Partnerships with state and local agencies and industry groups should be established and are critical to success. The Lewiston Roundup may want to establish a dialog with the relevant state and local agencies (DEQ, Department of Water Resources, etc) related to wellhead protection.

IOC = inorganic chemical, VOC = volatile organic chemical, SOC = synthetic organic chemical

Due to the time involved with the movement of ground water, drinking water protection activities should be aimed at long-term management strategies even though these strategies may not yield results in the near term. A strong public education program should be a primary focus of any drinking water protection plan. There are multiple resources available to help communities implement protection programs, including the Drinking Water Academy of the U.S. EPA. For areas where transportation corridors transect the delineation, the Department of Transportation should be included in protection activities. Drinking water protection activities for agriculture should be coordinated with the Idaho State Department of Agriculture, the Soil Conservation Commission, the local Soil Conservation District, and the Natural Resources Conservation Service.

Assistance

Public water suppliers and others may call the following DEQ offices with questions about this assessment and to request assistance with developing and implementing a local protection plan. In addition, draft protection plans may be submitted to the DEQ office for preliminary review and comments.


Lewiston Regional DEO Office (208) 799-4370

State DEQ Office (208) 373-0502

Website: http://www2.state.id.us/deq

Water suppliers serving fewer than 10,000 persons may contact John Bokor, Idaho Rural Water Association, at 1-800-962-3257 for assistance with drinking water protection (formerly wellhead protection) strategies.

Lewiston Roundup





1B (3 yr TOT)

- Enhanced Inventory
- **CERCLIS Site**
- **RICRIS Site**
- LUST Site
- Closed UST Site
- Open UST Site
- **Business Mailing List**
- NPDES Site
- Toxic Release Inventory
- SARA Title III Site (EPCRA)
- Recharge Point
- Injection Well
 - Group1 Site
- Cyanide Site
- Landfill
- Wastewater Land App.Site

Neither the State of Idaho nor the Idaho Department of Environmental Quality, nor any of their employees make any warranty, express or implied, or assume any legal liability or responsibility for the accuracy, completeness or usefulness of any information or data provided. Metadata is provide for all data sets, and no data should be used without first reading and understanding its limitations. The data could include technical inaccuracies or typographical errors. The Department of Environmental Quality may update, modify, or revise the data used at any time, without

POTENTIAL CONTAMINANT INVENTORY LIST OF ACRONYMS AND DEFINITIONS

<u>AST (Aboveground Storage Tanks)</u> – Sites with aboveground storage tanks.

<u>Business Mailing List</u> – This list contains potential contaminant sites identified through a yellow pages database search of standard industry codes (SIC).

<u>CERCLIS</u> – This includes sites considered for listing under the Comprehensive Environmental Response Compensation and Liability Act (CERCLA). CERCLA, more commonly known as Asuperfund@is designed to clean up hazardous waste sites that are on the national priority list (NPL).

<u>Cyanide Site</u> – DEQ permitted and known historical sites/facilities using cyanide.

<u>Dairy</u> – Sites included in the primary contaminant source inventory represent those facilities regulated by Idaho State Department of Agriculture (ISDA) and may range from a few head to several thousand head of milking cows.

<u>Deep Injection Well</u> – Injection wells regulated under the Idaho Department of Water Resources generally for the disposal of stormwater runoff or agricultural field drainage.

Enhanced Inventory – Enhanced inventory locations are potential contaminant source sites added by the water system. These can include new sites not captured during the primary contaminant inventory, or corrected locations for sites not properly located during the primary contaminant inventory. Enhanced inventory sites can also include miscellaneous sites added by the Idaho Department of Environmental Quality (IDEQ) during the primary contaminant inventory.

<u>Floodplain</u> – This is a coverage of the 100year floodplains.

<u>Group 1 Sites</u> – These are sites that show elevated levels of contaminants and are not within the priority one areas.

<u>Inorganic Priority Area</u> – Priority one areas where greater than 25% of the wells/springs show constituents higher than primary standards or other health standards.

<u>Landfill</u> – Areas of open and closed municipal and non-municipal landfills.

<u>LUST</u> (<u>Leaking Underground Storage Tank</u>) — Potential contaminant source sites associated with leaking underground storage tanks as regulated under RCRA.

<u>Mines and Quarries</u> – Mines and quarries permitted through the Idaho Department of Lands.)

<u>Nitrate Priority Area</u> – Area where greater than 25% of wells/springs show nitrate values above 5mg/l.

NPDES (National Pollutant Discharge Elimination System) — Sites with NPDES permits. The Clean Water Act requires that any discharge of a pollutant to waters of the United States from a point source must be authorized by an NPDES permit.

<u>Organic Priority Areas</u> – These are any areas where greater than 25 % of wells/springs show levels greater than 1% of the primary standard or other health standards.

<u>Recharge Point</u> – This includes active, proposed, and possible recharge sites on the Snake River Plain.

RICRIS – Site regulated under Conservation Recovery Act (RCRA). RCRA is commonly associated with the cradle to grave management approach for generation, storage, and disposal of hazardous wastes.

SARA Tier II (Superfund Amendments and Reauthorization Act Tier II Facilities) – These sites store certain types and amounts of hazardous materials and must be identified under the Community Right to Know Act.

Toxic Release Inventory (TRI) – The toxic release inventory list was developed as part of the Emergency Planning and Community Right to Know (Community Right to Know) Act passed in 1986. The Community Right to Know Act requires the reporting of any release of a chemical found on the TRI list.

<u>UST (Underground Storage Tank)</u> – Potential contaminant source sites associated with underground storage tanks regulated as regulated under RCRA.

<u>Wastewater Land Applications Sites</u> – These are areas where the land application of municipal or industrial wastewater is permitted by IDEQ.

<u>Wellheads</u> – These are drinking water well locations regulated under the Safe Drinking Water Act. They are not treated as potential contaminant sources.

NOTE: Many of the potential contaminant sources were located using a geocoding program where mailing addresses are used to locate a facility. Field verification of potential contaminant sources is an important element of an enhanced inventory.

Where possible, a list of potential contaminant sites unable to be located with geocoding will be provided to water systems to determine if the potential contaminant sources are located within the source water assessment area.

The final scores for the susceptibility analysis were determined using the following formulas:

- 1) VOC/SOC/IOC Final Score = Hydrologic Sensitivity + System Construction + (Potential Contaminant/Land Use x 0.273)
- 2) 2) Microbial Final Score = Hydrologic Sensitivity + System Construction + (Potential Contaminant/Land Use x 0.35)

Final Susceptibility Scoring:

- 0 5 Low Susceptibility
- 6 12 Moderate Susceptibility
- ≥ 13 High Susceptibility

Public Water System Name :

LEWISTON ROUNDUP

Well# : N WELL #1 Public Water System Number 2350016 2/14/02 10:44:05 AM

System Construction		SCORE						
Drill Date	1/26/82							
Driller Log Available	NO NO							
Sanitary Survey (if yes, indicate date of last survey)	YES	1996						
Well meets IDWR construction standards	NO NO	1						
Wellhead and surface seal maintained	YES	0						
Casing and annular seal extend to low permeability unit	NO	2						
Highest production 100 feet below static water level	NO NO	1						
Well located outside the 100 year flood plain	NO NO	1						
	NO							
	Total System Construction Score	Total System Construction Score 5						
Hydrologic Sensitivity								
Soils are poorly to moderately drained	NO	2						
Vadose zone composed of gravel, fractured rock or unknown	YES	1						
Depth to first water > 300 feet	NO	1						
Aquitard present with > 50 feet cumulative thickness	NO	2						
	Total Hydrologic Score	Total Hydrologic Score 6						
		IOC	VOC	SOC	Microbi			
Potential Contaminant / Land Use - ZONE 1A		Score	Score	Score	Score			
Land Use Zone 1A	IRRIGATED PASTURE	1	1	1	1			
Farm chemical use high	YES	2	0	2				
IOC, VOC, SOC, or Microbial sources in Zone 1A	NO	NO	NO	NO	NO			
Total Potentia	al Contaminant Source/Land Use Score - Zone 1A	3	1	3	1			
Potential Contaminant / Land Use - ZONE 1B								
Contaminant sources present (Number of Sources)	YES	4	3	3	3			
(Score = # Sources X 2) 8 Points Maximum		8	6	6	6			
Sources of Class II or III leacheable contaminants or	YES	4	3	3				
4 Points Maximum		4	3	3				
Zone 1B contains or intercepts a Group 1 Area	NO	0	0	0	0			
Land use Zone 1B	Greater Than 50% Non-Irrigated Agricultural	2	2	2	2			
Total Potential	Contaminant Source / Land Use Score - Zone 1B	14	11	11	8			
Cumulative Potential Contaminant / Land Use Score		17	12	14	9			
Final Susceptibility Source Score		16	14	 15	14			
Final Well Ranking		High	High	High	High			

Public Water System Name :

LEWISTON ROUNDUP
Public Water System Number 2350016

1. System Construction Drill Date 1/26/82 Driller Log Available NO Sanitary Survey (if yes, indicate date of last survey) YES 1996 Well meets IDWR construction standards NO 1 Wellhead and surface seal maintained YES Λ Casing and annular seal extend to low permeability unit NO 2 Highest production 100 feet below static water level NO 1 Well located outside the 100 year flood plain Soils are poorly to moderately drained NO YES Vadose zone composed of gravel, fractured rock or unknown 1 NO Depth to first water > 300 feet 1 Aguitard present with > 50 feet cumulative thickness Total Hydrologic Score 6 Score 3. Potential Contaminant / Land Use - ZONE 1A Score Score Score

 Land Use Zone 1A
 IRRIGATED PASTURE
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 1
 2
 0
 2
 0
 2
 0
 0
 NO
 Land Use Zone 1A IRRIGATED PASTURE Farm chemical use high YES IOC, VOC, SOC, or Microbial sources in Zone 1A Potential Contaminant / Land Use - ZONE 1B 3 Contaminant sources present (Number of Sources) 4 3 3 (Score = # Sources X 2) 8 Points Maximum 8 6 6 3 3 Sources of Class II or III leacheable contaminants or 4 YES 3 4 4 Points Maximum 3 pts a Group 1 Area NO 0 0 Land use Zone 1B Greater Than 50% Non-Irrigated Agricultural 2 2 Zone 1B contains or intercepts a Group 1 Area 0 Total Potential Contaminant Source / Land Use Score - Zone 1B 14 11 11 8 Cumulative Potential Contaminant / Land Use Score

Well# : W WELL #2

2/14/02 10:44:42 AM

Public Water System Name :

Public Water System Number 2350016

LEWISTON ROUNDUP

1. System Construction Drill Date Driller Log Available YES Sanitary Survey (if yes, indicate date of last survey) YES 1996 Well meets IDWR construction standards 1 Wellhead and surface seal maintained Ω Casing and annular seal extend to low permeability unit Highest production 100 feet below static water level Well located outside the 100 year flood plain 2. Hydrologic Sensitivity Soils are poorly to moderately drained NO Vadose zone composed of gravel, fractured rock or unknown YES 1 Depth to first water > 300 feet Aguitard present with > 50 feet cumulative thickness ______ Total Hydrologic Score 4 SOC Microbial Score Score Score 3. Potential Contaminant / Land Use - ZONE 1A Score Land Use Zone 1A IRRIGATED PASTURE
Farm chemical use high YES
IOC, VOC, SOC, or Microbial sources in Zone 1A NO emical use high YES 2 0 2
rces in Zone 1A NO NO NO NO
Total Potential Contaminant Source/Land Use Score - Zone 1A 3 1 3 Potential Contaminant / Land Use - ZONE 1B 1 0 0 Ω Contaminant sources present (Number of Sources) X 2) 8 Points Maximum 2 0 0 0

acheable contaminants or YES 1 0 0

4 Points Maximum 1 0 0

.ntercepts a Group 1 Area NO 0 0

Land use Zone 1B Greater Than 50% Non-Irrigated Agricultural 2 2 2 (Score = # Sources X 2) 8 Points Maximum Ω Sources of Class II or III leacheable contaminants or YES Zone 1B contains or intercepts a Group 1 Area Total Potential Contaminant Source / Land Use Score - Zone 1B

Well# : SOUTHSIDE #3

2/14/02 10:44:22 AM